LANDSCAPING NOTES:
CONTRACTOR TO HYDROSEED AND REESTABLISH GROUNDCOVER PER MNDOT SPECIFICATIONS LISTED:
2574.507 Common Topsoil Borrow 6" (CV)
2574.508 Fertilizer Type 3
2575.508 Hydraulic Reinforced Fiber Matrix
2575.508 Seed Mixture MnDOT 25-151 High Maintenance Turf

GRADING NOTES:
FIELD VERIFY EXISTING GRADES
PROTECT ALL EXISTING FEATURES
COORDINATE CONSTRUCTION ACCESS W/PUBLIC WORKS
PROTECT FINISHED CONCRETE UNTIL HARD - DAMAGE CAUSED BY OTHERS IF SITE IS NOT SECURED WILL BE REPAIRED AT CONTRACTOR EXPENSE

EROSION CONTROL NOTES:
THE CONTRACTOR SHALL INSURE SEDIMENT CONTROL MEASURES ARE ESTABLISHED ON ALL DOWN GRADIENT PERIMETERS BEFORE ANY UPGRADIENT LAND DISTURBING ACTIVIIES BEGIN. THESE MEASURES SHALL BE REMAIN IN PLACE UNTIL FINAL STABILIZATION HAS BEEN ESTABLISHED.

8"

Erosion Control Log

STAKE LAYOUT FOR APPROVAL BY OWNER PRIOR TO POUR

781.48

784.32

784.70

784.34

37'-8"

35'-1"

38'-0"

1%

1%

SLOPE TO DRAIN
2% MIN

CONCRETE PAD TO BE BUILT PER ATTACHED PLANS WITH REINFORCEMENT AND DETAILING AS SHOWN ON PLANS

*PLEASE PROVIDE ALTERNATE PRICE FOR USING 3/8" FIBERGLASS REBAR AT 3'-0" OC BOTH WAYS INSTEAD OF 6 X 6 WWF

20'

784.14

784.34

784.70

784.32

5'

SLOPE TO DRAIN
2% MIN

784.14

782.48

WALK TO START 168' FROM CENTERLINE OF VIERLING GREENWAY TRAIL TO NORTH

Construction Limits

3181 782.60 edge of bit
3182 782.56 edge of bit
3184 784.80 edge of bit
3183 784.73 edge of bit
3300 781.49 break line
3301 782.29 break line
3302 782.25 break line
3353 783.49 break line
3354 783.37 break line
3355 783.32 break line E
3093 782.49 break line E

City of Shakopee
8/4/2023

Scenic Heights Park
1195 Ruby Lane, Shakopee, MN 55379

Concrete Pad - Grading and Erosion Control Plan

National Fitness Campaign